F10a

City of Hiawatha

Engineering Department

101 Emmons St., Hiawatha Iowa, 52233-1697
PHONE (319) 393-1515 ext. 511 FAX (319) 393-1516

To: Mayor and City Council

Date: February 5, 2017

From: John C Bender PE, City Engineer

Re: Emmons Street/NCPR/Robins Road Phase I Utility Project

Description: Change Order #5

Report:

Change Order #5: The plans called for an open trench construction for water main on Robins Road. The contractor proposed boring the water main pipe under the street and driveways for the same cost as the open trench plan. This process saved us from closing Robins Road for a second time and was included in change order #3.

The pipe material used for a drilling operation is a more costly locking joint pipe that needed to be used in order for the pipe to be pulled from one open boring pit to the other. The more expensive pipe was used in order for the process to be successful at an extra cost of material only at $7.49/foot of pipe.

Engineering recommends approval of change order No 5 for a cost increase of $2,846.20 for the change in pipe materials.

If you need any further information, please let me know.

CHANGE ORDER NO. 5

PROJECT: EMMONS STREET/NORTH CENTER POINT ROAD/ROBINS ROAD INTERSECTION IMPROVEMENTS PHASE I-UTILITY PACKAGE

DATE: May 17, 2016

CONTRACTOR: Ricklefs Excavating, Ltd
Anamosa, Iowa

ORIGINAL CONTRACT AMOUNT: $ 810,269.93

ORIGINAL CONTRACT COMPLETION DATE: August 19, 2016

ITEM #1.7: **ADD NEW ITEM-** Increase cost of pipe material used in change order #3 due to the fact that 8" water main pipe to be bored must be changed from standard 8" PVC pipe to 8" certa lok pipe DR18 at an additional cost of $7.49/foot. Add cost of 380 feet of ceta lok pipe material only at $7.49/foot. Lump sum cost $2,846.20.

CHANGES IN SCHEDULE: No additional time change for this change order.

CHANGE ORDER No. 5 SUMMARY:

Item No.	Description	Unit	Unit Price	Quantity	Total Amount
1.7	Add cost of certa lock pipe for 380 feet of 8"	LS	$ 2,846.20	1	$2,846.20
				Subtotal:	$2,846.20

Additional Change Order No. 5 Cost: $2,846.20

Ricklefs Excavating, Ltd.

By: _____

Title: _____

Date: _____

Attest

By: _____

Title: _____

Date: _____

City of Hiawatha, Iowa

By: _____

Title: _____

Date: _____

PRICE QUOTATION

SCHIMBERG CO.
1106 Shaver Road NE
Cedar Rapids, IA 52402
Ph: 319-365-9421 FAX: 319-365-9867
www.schimberg.com

Quote Date	12/12/16
Quote Number	7565542-00
Quote Expiration Date	12/12/16
Writer	Scott McMurrin
Salesperson	SCOTT MCMURRIN
Total Weight	1310.59500
Freight Terms	SAMPLE PRICING
Placed By	CORY

Bill To: 4949	RICKLEFS EXCAVATING LTD 12536 BUFFALO RD ANAMOSA, IA 52205

Ship To:	RICKLEFS EXCAVATING LTD SAMPLE PRICING ANAMOSA, IA 52205

PHONE:(319) 462-4435
EMAIL:PDAVILLE@schimberg.com

Terms	Req Ship Date	Ship Point	Ship Via
NET 30 DAYS	12/12/16	SCHIMBERG CEDAR RAPIDS	S CO TRUCK

Line #	NS	Part Number And Description	Quantity Ordered	Qty U/M	Net Price	Ext. Price
1		**56002010800** PIPE PVC C900 DR18 WM 8X20	20.0	FT	9.06	181.20
2		**56001020800** CERTA LOK PIPE DR18 RJIB 8X20' SUPPLIED WITH 32" SPLINES	20.0	FT	16.55	331.00
3		**52002010800** CL52 PIPE DI WM PUSH JT 8X18'6 WITH PUSH GASKET 8"	18.5	FT	16.54	305.99
4		**51202010800** CL52 PIPE DI TR FLEX 8X18'6 W/ 1 3/4x8-1/4 RUBBER LOCK SEGMENT & 1 LEFT & 1 RIGHT RETAINER	18.5	FT	30.80	569.80

4 Lines Total **Sales Tax Will Apply** *Quote Total* 1,387.99

SALESPERSON CONTACT INFORMATION
Scott McMurrin
smcmurrin@schimberg.com

If "NS" is indicated in the "NS" column or any part number beginning with an "N" or "W" is non-stock material and subject to manufacturers restock & return freight charges.

--- The prices quoted are subject to inventory availability and changes in raw material costs. ---

--- Jobs with multiple shipments or a duration of more than 30 days must be authorized in advance. ---

DRAFT

RESOLUTION NO. 17-
City Council

RESOLUTION APPROVING CHANGE ORDER #5
FY 2015-2017 Emmons Street/North Center Point Road/Robins Road Intersection Improvements Project
(Project #2151330)

WHEREAS, the City Council of the City of Hiawatha, Iowa, has contracted for the FY 2015-2017 Emmons Street/North Center Point Road/Robins Road Intersection Improvements Project with Ricklefs Excavating, Ltd. of Anamosa, Iowa, and

WHEREAS, the City Engineer has recommended Change Order #5 for adjustment of contract quantities with an increase of $2,846.20, bringing the total revised contract amount to $813,116.13, for the FY 2015-2017 Emmons Street/North Center Point Road/Robins Road Intersection Improvements Project, and

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF HIAWATHA, IOWA, to approve Change Order #5 for the FY 2015-2017 Emmons Street/North Center Point Road/Robins Road Intersection Improvements Project with an increase in contract amount of $2,846.20, resulting in a revised total project contract amount of $813,116.13.

AYES:
NAYS:
ABSENT:

PASSED AND APPROVED this 15th day of February, 2017.

_____
Bill Bennett, Mayor

ATTEST:

_____
Kelly Kornegor, City Clerk